

Gardner Field Renovation Project Recommended *Minimum* Tools List Total Project – Purchased Play Equipment Only

Main Office
1800 Mearns Road
Suite GG
Warminster, PA 18974

Mail
P.O. Box 883
Doylestown, PA 18901


Phone
866.464.7529
215.675.4718

Fax
215.675.8702

Email
Design@
DesignedForFun.com

Website
DesignedForFun.com

<u>Quantity</u>	<u>Excavation Tools (for Post Hole Clean-out)</u>
10	Shovels, round end, long handle
4	Flat edge shovels
8	Post hole diggers
8	Metal rakes
10	Wheelbarrows
4	Heavy-duty steel pry bars (breaker bars)
6	pitch forks
	 <u>Electrical Tools</u>
1	Generator or electrical source
8	Heavy-duty extension cords (100' long)
4	Electric impact wrenches (very important !)
2	Circular saw
4	Heavy duty drills with 1/2" chuck
2	Belt sander with additional coarse grit belts
1	Router with 3/8" round-over bit
4	Multiple plug power splitters
	 <u>Small Hand Tools & Miscellaneous</u>
1	Wood chisel (1")
2	Crow bar
1	Roll of duct tape
6	Heavy duty ratchet straps
2	Hydraulic "bottle" jacks, two ton or car jack
2	Hand saw
20	Claw hammers (ideally one per person)
4	Sledge hammers , 8 LB
10	Bar clamps, wide jaw, 24" long (very important !)
14	Socket wrenches, 1/2" drive (more would help)
6	T-55 TORX hex bits for 1/2" drive (very important!)
4	1/2" sockets, to fit 1/2" drive socket wrench
8	9/16" sockets, to fit 1/2" drive socket wrench
2	3/4" sockets, to fit 1/2" drive socket wrench
6	T- TORX Bit drivrs
2	Adjustable wrenches
2	Channel lock pliers



Gardner Field Renovation Project Recommended *Minimum* Tools List Total Project – Purchased Play Equipment Only

Small Hand Tools & Miscellaneous

- | | |
|--|--|
| 6
1
2
1
2
3
2
3
2
6
6
2
8
10
8
10 | Vice Grips pliers
Wood boring "spade" bit, 1" diameter
Wood boring "spade" bit, 1-1/8" diameter
Wood boring "spade" bit, 1-1/2" diameter
Drill bit, 1/2" x 12" long
Drill bit, 3/8" x 12" long
Bolt cutters
Wire cutters or sheet metal shears (to cut banding)
Hack saw with spare blades (or electric "Sawz All")
Utility Knives with spare blades
25' measuring tapes
Framing squares
Ratchet straps, at least 15 feet long
Steel form pins for holding braces & ratchet straps
Step ladders, 8' minimum,
55 gallon drums for trash or 10 cubic yard dumpster |
|--|--|

Consumable Items for Construction

- | | |
|--------------------|---|
| 30 pieces
3 lb. | 2" x 4" x 8' or longer, cheap lumber for temporary bracing. We can also use any small length scraps that someone may have laying around the house/shop/yard. These small pieces can be used for shims beneath the longer pieces or for stakes

TORX Head Deck Screws- 3" long |
|--------------------|---|

Main Office
1800 Mearns Road
Suite GG
Warminster, PA 18974

Mail
P.O. Box 883
Doylestown, PA 18901

Phone
866.464.7529
215.675.4718

Fax
215.675.8702

Email
Design@
DesignedForFun.com

Website
DesignedForFun.com